
|                   | L PRICES ARE INCLUSIVE OF TRANSPORT, LABOU BILL OF QUANTITIES  |            |          |                         |               |
|-------------------|--|------------|----------|-------------------------|---------------|
| Item              | Description  | Unit       | Qty      | Rate (Ksh)              | Amount (Kshs) |
| Bill 1            | GENERAL ITEMS / PRELIMINARIES  |            |          |                         |               |
| 1.1               | Allow for mobilization of machinery, equipment and personel for due satisfactory implementation of the works and demobilization from site after completion, provision of security, personal protective equipments and insurance of works | Item       | 1        |                         |               |
| 1.2               | Supply and erect publicity sign board on 1.5m x 1.2m metal sheet approximately secured on a 40 mm x 3mm thick steel frame at least 2m above the ground level and leveled as directed   | No         | 1        |                         |               |
|                   | Sub total carried for collection in the summary page   |            |          |                         | •             |
| Bill              | B) REHABILTATION OF 200 CUBIC METER RC A   | ND PUM     | PING SY  | STEM                    |               |
| Item              |  | Unit       | Qty      | Rate                    | Amount        |
| 2.1               | Desilting and removal of sand and cleaning of the sump   | СМ         | 200      | Electrical and a second |               |
| 2.2               | Allow for dewatering of sump to keep away all waters during rehabilitation works. Inclusive where necessary pumping, river diversion   | Item       | 1        |                         |               |
|                   | Replace the top reinforced manhole cover of the sump as directed by the supervising engineer   | No         | 2        |                         | 4             |
| 2.3               |  | -          |          |                         |               |
| 2.3               | Supply, and reinstal 4 mm sq x 4 core armoured / submersible cable   | LM         | 50       |                         |               |
|                   | Supply, and reinstal 4 mm sq x 4 core armoured /   | LM<br>LM   | 50<br>50 |                         |               |
| 2.4               | Supply, and reinstal 4 mm sq x 4 core armoured / submersible cable  Supply, and reinstal 1.5 mm sq x 2 core armoured   |            |          |                         |               |
| 2.4               | Supply, and reinstal 4 mm sq x 4 core armoured / submersible cable  Supply, and reinstal 1.5 mm sq x 2 core armoured sensor cable  Retrieve, service and reinstall existing pump as  | LM         | 50       |                         |               |
| 2.4<br>2.5<br>2.6 | Supply, and reinstal 4 mm sq x 4 core armoured / submersible cable  Supply, and reinstal 1.5 mm sq x 2 core armoured sensor cable  Retrieve, service and reinstall existing pump as directed by the supervising engineer                 | LM<br>Item | 50       |                         |               |





| NO. | ITEM DESCRIPTION  | UNIT     | QTY         | RATE            | AMOUNT                |
|-----|---|----------|-------------|-----------------|-----------------------|
| NO. | Rising Main Pineline (Pobel-11)   |          | 200 mm m    |                 | KSHS.                 |
| 100 | Rising Main Pipeline (Rehabilitation of rising main   | from St. | Bakita to I | Elevated tank)  |                       |
| 3.1 | per engineer's specifications (trench minimum depth 750 mm), lay, test pipeline and backfill to ground level for item below   | LM       | 4300        | *n 1            |                       |
| 3.2 | Supply, deliver, install and test O/D 90 mm (3")<br>HDPE pipes PN16 as per KS ISO 4427:2007. To be<br>laid in the same trench as item 3.1 above   | LM       | 1000        |                 |                       |
| 3.3 | Supply, deliver, install and test O/D 90 mm (3")<br>HDPE pipes PN12.5 as per KS ISO 4427:2007. To be<br>laid in the same trench as item 3.1 above   | LM       | 3300        |                 |                       |
| 3.4 | Butt fusion for item 3.2 and 3.3 above  | Item     | l/sum       |                 |                       |
| 3.5 | Provide for HDPE 3" x 1.5" tee (not clamp) for installation of air valve along the pipeline above as directed by supervising engineer   | No       | 5           |                 |                       |
| 3.6 | Supply and install 50 mm (1.5") single orifice air valves   | No       | 5           |                 |                       |
| 3.7 | Supply, deliver, install and test O/D 90 mm (3") G.I pipes class B 6 M Lengths. Rate to include welding, cutting, threading and joining at the Elevated Tank as directed superving engineer | No.      | 3           |                 |                       |
| 3.8 | Distribution Pipeline (Rehabilitation of return pipel   | ine from | Kiangini M  | farket to St. B | akita)                |
| 3.9 | Bush clearing and excavation to replace existing pipe as per engineer's specifications (trench minimum depth 600 mm), lay, test pipeline and backfill to ground level for item below        | LM       | 1000        |                 |                       |
| 3.1 | Supply, deliver, install and test O/D 63 mm (2") HDPE pipes PN12.5 in 100 m rolls as per KS ISO 4427:2007. To be laid in the same trench as item above from Kiangini Market to St. Bakita   | LM       | 1000        |                 |                       |
| .11 | 90 mm x 63 mm HDPE reducer  | No       | 1           |                 |                       |
| .12 | Provision of 90mm X 63mm tee at Kwa Chief<br>Culvert for distribution pipeline to ICT   | Unit     | 1           |                 |                       |
| .13 | Butt fusion for item 3.10 above   | Item     | 1/sum       |                 | The State of the Land |





| 3.14 | Supply and install 90mm (3") Gate valves (Pegler PN 16 or equivalent as approved by supervising engineer) c/w flanged type together with fittings  | No  | 1    |          |  |
|------|--|-----|------|----------|--|
| 3.15 | Supply, joint and test 63 mm (2") end cap  | No. | 1    |          |  |
| 3.16 | Pipeline From Kwa Chief Culvert to ICT   |     |      |          |  |
| 3.17 | Bush clearing and excavation of trench as per<br>engineer's specifications (trench minimum depth 600<br>mm), lay, test pipeline and backfill to ground level<br>for item 3.18 below            | LM  | 500  |          |  |
| 3.18 | Supply, deliver, install and test O/D 63 mm (2") HDPE pipes PN12.5 in 100 m rolls as per KS ISO 4427:2007. To be laid in the same trench as item above and connected as per item 3.17 above    | LM  | 500  |          |  |
| 3.19 | Supply, deliver, install and test O/D 63 mm (2") HDPE connectors   | No  | 6    |          |  |
| 3.2  | Supply and install 63 mm (2") Pegler Gate valves or equivalent as approved by supervising engineer) c/w fittings   | No  | 3    |          |  |
| 3.21 | Supply and install 50 mm (1.5") Pegler Gate valves or equivalent as approved by supervising engineer) c/w fittings   | No  | 1    |          |  |
| 3.22 | Construct communal water point at ICT as directed by supervising engineer c/w 3/4 meter, gate valve, and G.I outlet  | No. | 1    | <i>y</i> |  |
| 3.23 | Pipeline to Muthwani Secondary   |     |      |          |  |
| 3.24 | Bush clearing and excavation to to pipe invert level as per engineer's specifications (trench minimum depth 600 mm), lay, test pipeline and backfill to ground level for item 3.25 below       | LM  | 2300 |          |  |
| 3.25 | Supply, deliver, install and test O/D 50 mm (11/2") HDPE pipes PN12.5 in 100 m rolls as per KS ISO 4427:2007. To be laid in the same trench as item above and connected as per item 3.24 above | LM  | 2300 |          |  |
| 3.26 | Supply, deliver, install and test O/D 50 mm (1.5") HDPE connectors for item above  | No  | 24   |          |  |
| 3.27 | Supply and install 63mm X 50mm Tee as approved by supervising engineer) c/w fittings   | No  | 1    | 16.0     |  |





| 3.28        | Supply and install 50 mm (1.5") Pegler Gate valves or equivalent as approved by supervising engineer) c/w fittings   | No  | 1   |       |        |
|-------------|--|---|-----|-------|--------|
| 3.29        | Provide for HDPE tee 50 mm (1.5") (not clamp) for installation of air valve along the pipeline above as directed by supervising engineer                               | No  | 2   |       |        |
| 3.3         | Supply and install 50 mm (1.5") single orifice air valves  | No  | 2   |       |        |
| 3.31        | Construct communal water point at muthwani as directed by supervising engineer c/w 3/4 meter, gate valve, and G.I outlet   | No.   | 1   |       |        |
|             | Sub Total carried for collection in the summary page   |   |     |       |        |
|             |  |   |     |       |        |
| BILL<br>No. | D) 10 CM TANK PLATFORM DESCRIPTION   | UNIT  | OTY | RATE  | AMOUNT |
| .NO.        | DESCRIPTION  | UNII  | QTY | KShs. | KShs.  |
|             | Supply materials and provide personnel to construct a tank base platform 1 m high to hold a 10 m <sup>3</sup> plastic water tank Muthwani (as in the attached drawing) |   |     |       |        |
| 4.1         | Cut the spoil upto 200mm below G.L over tank base and remove all vegetable soil to temporary spoil heap.   | A STATE OF THE PARTY AND A STATE OF THE PARTY | 1.5 |       |        |
| 4.2         | Excavate foundation from stripped level over the tank site to depth n.e. 0.6m deep 300 mm wide and dispose soil as directed  | SM  | 10  |       |        |
| 4.3         | Mass concrete mix 1:4:8: in 50mm thick blinding to hardcore  | СМ  | 0.4 |       | 7      |
| 4.4         | 225mm thick dressed quarry stone walling   | SM  | 26  |       |        |
| 4.5         | Provided handle, cut, bend and fix 8 mm deformed steel bars on all alternate course of the wall  | Kgs   | 28  |       |        |
| 4.6         | Damp proof course  | LM  | 9.5 |       |        |
| 4.7         | Provide, pack and compact hardcore in 300 mm layers to fill the tank platform  | СМ  | 9   |       |        |
| 4.8         | Provided handle, cut, bend and fix 8 mm deformed steel bars on top slab  | Kgs   | 16  |       |        |
| 4.9         | Vibrated reinforced concrete mix 1:2:4 in 100 mm thick for slab  | СМ  | 1   |       |        |

Chief officer:

Dra Dra

| 4.10 | EXTERNAL PLASTER - 20mm thick 1:2 cement sand to exterior face of tank wall  | SM             | 10  |               |                 |
|------|--|----------------|-----|---------------|-----------------|
| 4.11 | Supply, Deliver & Install a 10 m <sup>3</sup> Double Laminated<br>Plastic Water Tank, c/w G.I 1.5" dia. Outlet &<br>Overflow Pipes. To be mounted on 1.5 m high<br>masonry tank platform | No.            | 1   |               |                 |
| 4.12 | Supply and install (1.5") GI for inlet as approved by supervising engineer) c/w fittings   | No             | 2   |               |                 |
|      | Sub total carried for collection in the summary page   |                |     |               | L L             |
| BILL | E) AIR/GATE VALVE CHAMBER  |                |     |               |                 |
| No.  | ITEM DESCRIPTION   | UNIT           | QTY | RATE<br>KShs. | AMOUNT<br>KShs. |
|      | Supply materials and provide personnel to construct a air/gate valve chamber (as in the attached drawing)  |                |     |               |                 |
| 5.1  | Cut the spoil upto 300mm below g.l. over the borehole chamber area and remove all vegetable soil to temporary spoil heap.  | M <sup>3</sup> | 0.5 |               |                 |
| 5.2  | Excavate foundation from stripped level over the borehole chamber site to depth n.e. 0.6m deep 300 mm wide and dispose soil as directed  | $M^3$          | 1   |               |                 |
| 5.3  | Mass concrete mix 1:4:8: in 50mm concrete slab   | M <sup>3</sup> | 0.5 |               |                 |
| 5.4  | 225mm thick dressed quarry stone walling   | M²             | 5   |               |                 |
| 5.5  | Provide and instal a lockable double steel Cover c/w padlock or a reinforced concrete cover as instructed  | No.            | 1   |               |                 |
| 5.6  | EXTERNAL PLASTER - 20mm thick 1:2 cement sand to exterior face of the valve chamber wall   | M²             | 4   |               |                 |
|      | Sub Total for 1 No valve chamber   |                |     |               |                 |
|      | Sub total carried for collection in the summary page (for 13 No)   | No.            | 13  |               |                 |
|      |  |                |     |               |                 |
| BILL | PROVISIONAL SUMS   | UNIT           | QTY | RATE          | AMOUNT          |
| G    |  |                |     |               | KSHS.           |



130 P.W

| 6.1  | Allow a Provisional sum of Kshs 350,000 for<br>Contingencies to be expended by project manager |         |        |      | 350,000.00 |
|------|--|---------|--------|------|------------|
|      | Sub Total carried for collection in the summary page   |         |        |      | 350,000.00 |
| BILL | GRAND SUMMARY  | UNIT    | QTY    | RATE | AMOUNT     |
|      |  |         |        | 8111 | KSHS       |
| Α    | GENERAL ITEMS/PRELIMINARIES  |         |        |      |            |
| В    | REHABILTATION OF 200 CUBIC METER RC AND  | PUMPINO | SYSTEM |      |            |
| С    | PIPELINES AND WATER CONNECTION   |         |        |      | -          |
| D    | TANK PLATFORM  |         |        |      | -          |
| Е    | VALVE CHAMBER  |         |        |      | -          |
| G    | PROVISIONAL SUMS   |         |        |      | 350,000.00 |
|      | TOTAL TAKEN TO TENDER FORM   |         |        |      |            |
|      |  |         |        |      |            |
|      | GRAND TOTAL  |         |        |      |            |



PDC M

Ge 188